

# **SANDIA REPORT**

SAND98-0481 • UC-1242

Unlimited Release

Printed March 1998

## **Final Report on the Design and Development of a Rolling Float Meter for Drilling-Fluid Outflow Measurement**

G. E. Staller, J. J. Westmoreland, G. L. Whitlow, E. K. Wright, D. A. Glowka

Prepared by

Sandia National Laboratories

Albuquerque, New Mexico 87185 and Livermore, California 94550

Sandia is a multiprogram laboratory operated by Sandia Corporation,  
a Lockheed Martin Company, for the United States Department of  
Energy under Contract DE-AC04-94AL85000.

Approved for public release; further dissemination unlimited.



**Sandia National Laboratories**

Issued by Sandia National Laboratories, operated for the United States Department of Energy by Sandia Corporation.

**NOTICE:** This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government, any agency thereof, or any of their contractors or subcontractors. The views and opinions expressed herein do not necessarily state or reflect those of the United States Government, any agency thereof, or any of their contractors.

Printed in the United States of America. This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from  
Office of Scientific and Technical Information  
P.O. Box 62  
Oak Ridge, TN 37831

Prices available from (615) 576-8401, FTS 626-8401

Available to the public from  
National Technical Information Service  
U.S. Department of Commerce  
5285 Port Royal Rd  
Springfield, VA 22161

NTIS price codes  
Printed copy: A03  
Microfiche copy: A01

SAND98-0481  
Unlimited Release  
Printed March 1998

**FINAL REPORT ON THE DESIGN AND DEVELOPMENT OF A  
ROLLING FLOAT METER FOR DRILLING-FLUID OUTFLOW  
MEASUREMENT**

G.E. Staller, J.J. Westmoreland, G.L. Whitlow, E.K. Wright, D.A. Glowka  
Geothermal Research Department  
Sandia National Laboratories  
P.O. Box 5800  
Albuquerque, NM 87185-1033

**Abstract**

Lost circulation, which is the loss of well drilling fluids to the formation while drilling, is a common problem encountered while drilling geothermal wells. The rapid detection of the loss of well drilling fluids is critical to the successful and cost-effective treatment of the wellbore to stop or minimize lost circulation. Sandia National Laboratories has developed an instrument to accurately measure the outflow rate of drilling fluids while drilling. This instrument, the Rolling Float Meter, has been under development at Sandia since 1991 and is now available for utilization by interested industry users. This report documents recent Rolling Float Meter design upgrades resulting from field testing and industry input, the effects of ongoing testing and evaluation both in the laboratory and in the field, and the final design package that is available to transfer this technology to industry users.

## **Acknowledgments**

The authors would like to acknowledge the technical support provided by Sandia Geothermal Research Department personnel, R. D. Jacobson and S. D. Knudsen during laboratory and field test evaluations of the Rolling Float Meter.

This work was sponsored by the U.S. Department of Energy, Office of Geothermal Technologies.

## TABLE OF CONTENTS

	Page
Background .....	1
Current Design Features .....	1
Laboratory Test Results .....	7
Field Test Location Summary .....	10
Field Test Results .....	12
Final Design Package .....	16
Conclusions .....	17
References .....	19
Appendix A: Drawing Package .....	A1
Appendix B: Recommended Procedures .....	B1

## **Background**

The common problem of well drilling fluid (mud) loss to the formation while drilling geothermal wells should be addressed promptly to minimize well completion costs. The added costs incurred as a result of this “lost circulation” for an average geothermal well are estimated to be from 5% to 10% of the total well cost<sup>1</sup>. Various methods to treat and control lost circulation are being investigated by the Geothermal Research Department at Sandia National Laboratories. All methods currently under consideration require accurate and prompt detection of drilling fluid loss in order to analyze the magnitude of the loss zone and minimize the lost circulation treatment costs. To detect drilling fluid loss, both an accurate inflow and outflow meter must be employed on the drill rig to monitor these flow rates while drilling.

The Rolling Float Meter (RFM), developed at Sandia beginning in 1991<sup>2</sup>, has been used to accurately measure the outflow flow rate of well drilling fluids<sup>3,4</sup> in a partially-filled return line pipe. Commercially available non-intrusive inflow meters, such as the current state-of-the-art clamp-on Doppler ultrasonic flow meter, have been successfully employed on drill rigs to measure fluid inflow rates<sup>5</sup>. These commercial inflow meters are being evaluated by Sandia and compared to the industry-standard pump-stroke counter inflow measuring technique. Comparing the real time inflow and outflow rates, while drilling, provides the fast response delta flow (outflow minus inflow) needed to detect and treat lost circulation.

This report addresses the current design of the Sandia RFM, the results of recent laboratory and field tests, and the final design package being made available to industry to produce and market this instrument.

## **Current Design Features**


As documented in Ref. #2 above, during development of the RFM several design configurations were examined before settling on the original field-prototype design. Using this design, several prototype units were built and loaned to interested drilling and well logging companies for field testing and evaluation. These prototype units basically consisted of a rotating polyurethane foam float wheel, with a counterbalance, attached to a horizontal support shaft and mounted in a sheet metal housing. A pendulum potentiometer was attached to the horizontal shaft in the housing to measure the angle (and thus the fluid depth) between the float wheel and the return pipe. After testing, the loaned meters were returned to Sandia for post-test evaluation. Results of these tests were mixed. When the RFM was loaned, an instruction manual on installation, calibration and operation was provided by Sandia. However, since this was still a developmental tool, instructions were not always followed as intended, and routine RFM maintenance was overlooked or neglected. We also found that the field-prototype design was not as robust as required for the rough handling encountered around drill rigs, and damage to the loaned units was common. The severe environmental conditions (high mud temperatures, abrasive cuttings,

corrosive fluids, etc.) that the meter was exposed to while drilling geothermal wells, was also worse than expected. Examination of the polyurethane foam float wheel revealed that the foam was being eroded away during operation because of the abrasiveness of the return mud/cuttings, especially at the elevated temperatures encountered during geothermal drilling operations.

Meetings and telephone conversations with industry users provided us with additional features to improve the RFM design and make it more useful and acceptable to industry. One user, Inteq, Inc., chose to redesign the prototype RFM housing, making it more sturdy, so it could be employed on return lines where a sudden over pressurization, as from a well kick, would not damage the meter housing. This improved housing RFM was returned to Sandia by Inteq after their field evaluations. Several features of this design were incorporated into our design upgrade to improve the robustness of the RFM. In addition, the Inteq unit was modified by Sandia to test other design features that were later incorporated into our upgrade. Improvements in the design of the RFM were begun by Sandia in late 1995. A complete design-upgrade drawing package was prepared, using AutoCADlt software, and these files are available to interested industry manufacturers.

To improve the wear resistance of the float wheel we chose to fabricate a wheel from thin sheet metal instead of foam. The shape selected was similar to the prototype polyurethane foam wheel, see *Figure 1*, and the material was type 304 stainless steel (SS). Another feature added to the wheel assembly was an adjustable stop plate that allowed the wheel to be positioned close to, but not touching, the bottom ID of the return line pipe. This permits the wheel to begin rotation at a much lower flow rate than that required to lift the wheel off the bottom ID before it can start to rotate. Since the wheel is counterbalanced on the RFM, the buoyancy difference between the two wheels was minimized; however, the additional mass of the SS wheel did require higher fluid flow velocities, in contact with the convex dimple upsets on the wheel periphery, to initiate rotation. We also found that during rotation the shape of the prototype wheel caused it to be pulled deeper into the fluid than desired. Subsequent laboratory testing with a SS wheel that employed fins instead of upsets on the wheel periphery, reference *Figure 2*, provided a solution to the start-up rotation problem and resulted in a more stable wheel (less bounce) on the agitated surface of the fluid at high (>500 gpm) flow rates.

Accumulations of mud and other debris on the wheel sometimes necessitated field adjustments to the counterbalance to maintain desirable wheel stability. Since the counterbalance on the prototype was located internal to the RFM housing, adjustments were difficult. Changes were therefore incorporated into the upgrade to move the counterbalance outside of the RFM housing and to also provide a port in the housing to allow access to the wheel shaft for attaching a portable field scale that is used to measure the counterbalance/wheel weight differential when making counterbalance adjustments. To protect the counterbalance from exposure to the harsh drill rig environment, it was installed in a commercial steel instrument enclosure (NEMA Type 4) that was attached to the outside of the RFM housing.









Figure 2

The resolution of the pendulum potentiometer, used to measure float-wheel-to-pipe angle and thus fluid depths in the return line pipe, was limited. The pendulum potentiometer was replaced with a rotary potentiometer to measure this angular displacement. The bias voltage applied to the rotary potentiometer was set higher than the voltage applied to the pendulum potentiometer, to provide a better output signal-to-noise ratio. In addition, a commercial precision speed-reducer gear box with a 4:1 multiplication factor was placed in series between the RFM shaft, used to measure the float-wheel-to-pipe angle, and the rotary potentiometer. This 4:1 increase per degree-of-change for the float angle, along with the higher output voltage signal, produced increased sensitivity to fluid depth (flow) in the outflow pipe. This equipment was mounted in the same instrument enclosure used to protect the counterbalance. Both the enclosure and this equipment were designed to be installed on either side of the RFM housing to facilitate access for calibration and maintenance when used on a drill rig.




**Figure 3**

One of the problems encountered during field evaluations of the prototype RFM were false flow indications. When outflow was terminated and debris in the return line pipe prevented the float wheel from resting on the bottom ID of the pipe (zero flow position), a false flow indication was presented. As documented in Ref. #3, during initial development of the RFM, rotational speed of the wheel was eliminated as a method to measure return-line pipe flow. However, when wheel rotation was integrated with float angle (flow) indication, an “if” statement could be programmed into the flow data equation, such that flow indication was only valid when wheel rotation was occurring. To measure wheel rotation, a Hall-effect magnetic sensor was attached to the wheel shaft, and a magnet, to actuate the sensor, was mounted on the wheel (*Figure 3*). The Hall-effect sensor is installed in a fabricated housing designed specifically for

this sensor and epoxied in place to provide a water-tight assembly. When in use on an operating RFM, if the measured wheel rotation is zero, then the RFM outflow indication is presented as zero. This technique presents a problem if the Hall-effect sensor fails or if the wheel is jammed and prevented from rotating when outflow is obviously present. We incorporate a switch in our data acquisition software to bypass the “if” command and override a false zero indication, until the problem can be identified and resolved.

With the RFM configured this way, we were able to measure fluid outflow rates as low as 50 gpm and detect fluid losses as small as 2% of flow (10 gpm loss at 500 gpm flow) under laboratory conditions, (see *Figure 4* ).




**Figure 4**

Intrinsically-safe barriers are provided on RFM electronics to meet the safety requirements of oil and gas drilling applications.


## Laboratory Test Results

The Sandia Wellbore Hydraulics Flow Facility (WHFF), operated by the Geothermal Research Department, was used extensively to test and evaluate the RFM before it was employed in field operations. As shown in the WHFF diagram in *Figure 5*, the fluid flow



rates can be controlled by metering valves and measured with magnetic and/or Doppler flow meters, and an independently measured flow loss can be introduced during testing to model a wellbore loss zone. Water was the primary fluid used during initial RFM testing, however, drilling muds were also used during final testing and evaluation prior to field application.

As stated previously the Sandia/Inteq modified RFM (MRFM) was altered to assess the upgrades prior to incorporating them into the final RFM design. This modified unit was then attached to the WHFF simulated return line, (*Figure 6*), for testing and evaluation.




**Figure 6**

These upgrades included: the SS wheel with fins, the externally adjustable counterbalance, the rotary potentiometer with the 4:1 ratio gear-box multiplier, and the Hall-effect sensor to monitor wheel rotation. The MRFM power supply and data-acquisition circuits were designed and assembled by Sandia, and the data was recorded using National Instruments, Corp., LabView software.

The MRFM was calibrated in the laboratory against a magnetic flowmeter (4" Yokogawa ADMAG). Typical

calibration data is shown in *Figure 7*. Testing was done to evaluate the effect of wheel




**Figure 7**

weight on MRFM operation. The counterbalance was adjusted to vary the wheel down-weight from 50g to as much as 1000g. The return line flow rate was set at 500 gpm for these tests. The counterbalance was adjusted to provide minimal float wheel bounce at 500 gpm and still achieve lift-off from the stop plate at 30 to 50 gpm. Lift-off from the stop plate is the point at which the MRFM begins to register fluid depth in the return line or

increasing flow. The best wheel down-weight for the MRFM was approximately 750g. Below 500g, wheel bounce was excessive, and above 1000g the flow required to lift the wheel off the stop plate was greater than 50 gpm. Additional testing was then conducted to evaluate the operation of the MRFM at various return line angles. The return line was positioned at the angles of, 2°, 5°, 8.5°, and 12°, and operational parameters like bounce, calibration, and minimum detectable loss were verified. No significant differences could be detected when the return line angle was changed. An opportunity to field test the MRFM became available when SNL was requested to oversee slimhole drilling operations for several exploratory geothermal wells. Prior to taking the MRFM to the field for

testing, a simulated return line pipe that modeled the expected field return line pipe was constructed at the WHFF and used to verify MRFM calibration and operation under these conditions.


Ktech Corporation, a technical contracting and manufacturing firm in Albuquerque, NM, was contracted by Sandia to fabricate and assemble a prototype RFM produced from our upgraded design package. This fabrication was done in parallel with MRFM laboratory testing, thus any changes resulting from MRFM testing could be quickly incorporated into the Ktech prototype RFM during production. No changes were required, and the completed RFM was delivered to Sandia on 10/22/96. This unit was installed on the WHFF and evaluated at various flow rates, return line angles and wheel down-weights. The RFM power supply and data-acquisition circuits were also designed and assembled by Sandia, and the data were recorded using National Instruments, Corp., LabView software. *Figure 8* shows a typical RFM calibration curve against the WHFF magnetic flowmeter at



the optimal operating parameters of 750g wheel down-weight with a return line angle of 8.5°. The flow required to lift the wheel off the stop plate was approximately 50 gpm, and the peak flow applied to the RFM was 925 gpm, which is the maximum output of the WHFF pump.

The majority of the initial testing on the RFM was completed using water as the simulated wellbore fluid. However, the RFM was used during the evaluation of several commercial non-intrusive inflow meters on the WHFF. These meters required the use of drilling fluid/mud to adequately assess their performance. Therefore, the RFM was operated

extensively with mud as the simulated wellbore fluid in the WHFF. *Figure 9* indicates a typical RFM calibration curve against the WHFF magnetic flowmeter while flowing drilling fluid/mud.



### Field Test Location Summary

The MRFM was installed on several geothermal exploratory slim hole drilling operations<sup>6</sup> involving Sandia. The wells were drilled by the U.S. Army on the McGregor Range of the Fort Bliss Military Reservation near El Paso, TX. This work began in November 1996.

The following is a short summary of MRFM use on these tests:

In all cases the MRFM was used only until a 4.5" casing was installed in the well and core drilling operations began.

#### Well 46-6

MRFM installed on 11/10/96 - 11/11/96.

MRFM calibrated on 11/11/96.

4.5" casing cemented and MRFM removed on 11/25/96.

Total depth of well drilled using MRFM was 707'.

MRFM operation time was approximately 14 days.

Well 45-5

MRFM installed on 12/17/96.

MRFM calibrated on 12/18/96.

4.5" casing cemented and MRFM removed on 1/14/97.

Total depth of well drilled using MRFM was 596'.

MRFM operation time was approximately 15 days.

Well 61-6

MRFM installed on 2/17/97.

MRFM calibrated on 2/17/97.

4.5" casing cemented and MRFM removed on 2/22/97.

Total depth of well drilled using MRFM was 630'.

MRFM operation time was approximately 5 days.

Well 51-8

MRFM installed on 3/9/97.

MRFM calibrated on 3/9/97.

4.5" casing cemented and MRFM removed on 3/28/97.

Total depth of well drilled using MRFM was 529'.

MRFM operation time was approximately 19 days.

The RFM was installed on two large-diameter geothermal well drilling projects at sites in California to evaluate the current design. The first test was conducted solely to evaluate the RFM in a large-diameter geothermal well drilling environment. The second RFM evaluation test was done in conjunction with tests being conducted by Sandia for the Geothermal Drilling Organization (GDO) to evaluate the effectiveness of nitrogen-foamed cement when used to treat lost circulation in geothermal wells. The RFM was used to assist in monitoring the results of the cementing technique during the drilling operation. The following is a short summary of these tests:

California Energy Company, Inc., Imperial Valley Geothermal Field, Well location - Del Ranch #10

RFM installed on 3/4/97.

RFM calibrated on 3/5/97.

RFM removed on 4/9/97.

RFM operation time was approximately 35 days.

California Energy Company, Inc., Coso Geothermal Field, Well location - Navy II 76B-18

RFM installed on 8/27/97.

RFM calibrated on 8/28/97.

RFM removed on 10/27/97.

RFM operation time was approximately 60 days.



## **Field Test Results**

### Slimhole Well Drilling

The MRFM was selected for use during the Fort Bliss slimhole drilling operations because of its availability and the opportunity to further evaluate the MRFM performance during actual drilling operations. The original prototype RFM had been evaluated under similar conditions, and direct comparisons could be made to MRFM operation and thus to upgrade-feature performance.

The MRFM mounting flange was installed on the return line and the MRFM attached to the flange. The return line was 6", schedule-40 steel pipe with the output end attached directly to the possum belly on the rig mud-tank shaker box. The return line was positioned at a 9.7° angle from the pitcher/flow nipple on the rig mud riser to the mud tank shaker box. The MRFM underwent constant vibration as a result of being attached directly to the shaker box. Under normal conditions vibration on a large diameter geothermal drill rig is a common problem; thus the vibration from the shaker box was a good method to evaluate vibration effects on the MRFM upgrades.

These wells were drilled at a high altitude, semi-arid desert location during late fall and winter. Ambient air temperature variations at the well site were extreme, often very cold at night and warm during the day. Since the MRFM was only utilized during rotary drilling of the first 500' to 700' of each well, only minor changes in drilling fluid temperatures were encountered.


The MRFM operated as designed during each drilling operation. The only significant problem encountered was a sudden offset in the no-flow voltage signal at one point. This occurred while drilling the second well. Investigation of the MRFM gear box-to-rotary potentiometer connections revealed that a shaft connecting collar was loose, allowing slippage between the gear box and rotary pot shafts. This connection was tightened and the MRFM recalibrated. Ambient thermal cycling may have contributed to this collar clamping problem. No additional occurrences of this type were noted. Locktite adhesive is now employed on all critical threads to prevent this type of slippage.

The MRFM was employed to monitor and detect lost circulation that was occasionally encountered while drilling these wells. It was also used by the driller to help maintain his drilling rate by monitoring fluid returns while drilling. This assisted him in making decisions concerning possible booting (filling or plugging) of the drill pipe annulus with rock chips. The outflow data helped him decide when bit pull-back, to wash out the well, was desirable and when adequate flow was reestablished so he could put weight back on the bit and continue drilling.

## Large-Diameter Well Drilling

The upgraded RFM was first employed on a large diameter geothermal drill rig at the California Energy Company, Inc., (CalEnergy) Imperial Valley Geothermal Field, Del Ranch #10 site. This well was drilled by CalEnergy, in an established geothermal field, as a production well for existing power plant utilization. The well is located near Calipatria, CA, and was drilled over a five-week period during the spring when air temperatures were mild both during the day and at night. Sandia was invited to conduct drilling fluid inflow and outflow instrument evaluations while this well was being drilled.

The RFM mounting flange was installed on the drilling fluid return line pipe during well spudding procedures. The return line was a 10", schedule-40 steel pipe and was positioned with a 9.8° slope from the pitcher/flow nipple on the rig mud riser to the mud tank. The RFM mounting flange was welded to the return line, as directed by Sandia, over a 6"-wide X 21"-long opening in the pipe. This opening was torch cut into the pipe, and the ragged edge from the cutting operation had to be ground smooth, along the 6" wide edges, in order for the RFM wheel axle to properly clear the 6" opening and operate correctly. The RFM mounting flange was positioned so access for installation and maintenance of the RFM was available from the drill-rig mud-tank work deck, (see *Figure 10*).




**Figure 10**

The RFM was secured to the mounting flange, and the float wheel was adjusted for zero-flow conditions. The RFM counterbalance was adjusted for approximately 750g float wheel down-weight. Calibration of the RFM against the drill-rig mud-pump stroke-counter was then completed.

The RFM, with several minor problems, operated satisfactorily during this five-week drilling period. The first problem

encountered, two days after starting to drill, was caused by a large piece of debris (probably clay knocked off the wellbore by a drill-pipe centralizer) becoming lodged between the float wheel fins and the float wheel mounting shaft. This prevented the float wheel from rotating, and thus a no-flow condition was displayed on the RFM data-acquisition monitor. When the clay was removed, and the wheel was free to rotate, the RFM was returned to normal operation. Another problem occurred with the Hall-effect sensor/float-wheel rotation-monitor several weeks into the operation. This was caused by the accumulation of a magnetic material (possibly magnetite or fine metal chips in the drilling fluid) on the float-wheel magnet. This material interfered with the Hall-effect

sensor signal and resulted in the rotation indicator circuit displaying a no-flow condition when, in fact, flow remained constant and the float wheel was rotating. When this material was removed from the magnet, the Hall-effect sensor worked properly. The magnet was cleaned periodically, but eventually it had to be replaced to maintain Hall-effect sensor operation. The magnet was replaced twice during the five-week drilling period. The last magnet was coated with an epoxy to minimize exposure of the magnet's surface to the drilling fluid. The final problem, although not causing a malfunction, exposed the RFM to extreme temperatures and pressure pulses. To maintain the drilling fluid temperatures below 160° F, the rig operator installed a mud chiller in the drilling fluid system. At one point in the drilling operation, while the drill string was being tripped to replace a bottom hole assembly, the mud was not being circulated and the downhole mud temperatures rose significantly. When drilling operations resumed and the hot mud returned to the surface it flashed to steam. Some of this flashing occurred in the return line pipe, causing the RFM float wheel to be suddenly forced high enough in the pipe to impact the top of the RFM housing. This flashing and float wheel impact occurred several times before cool mud was circulated to the surface and the flashing subsided. The RFM operated normally during the remainder of the drilling operation. Post-test inspection of the RFM float wheel revealed a bent fin, see *Figure 11*, but no other apparent damage



resulted from the high mud temperatures or flashing steam pulses. Since the fins are welded to the wheel, the bent fin was easily straightened.

The RFM was disassembled, inspected, cleaned and re-assembled in preparation for additional field testing. New bearings were installed in the wheel. A new magnet with a protective coating on all exposed surfaces was installed on the wheel to improve Hall-effect sensor reliability. In addition, an adapter plate for a hinge between the RFM housing and the RFM pipe flange was designed and fabricated to enable an operator to

easily disconnect and rotate the RFM assembly off the pipe flange, for field repairs or maintenance, while it still remains attached to the return line pipe.


The second field test for the upgraded RFM was at another CalEnergy site. This well was in the Coso Geothermal Field, on the U.S. Navy's China Lake Naval Weapons Center located near Ridgecrest, CA. This new production well was located at the Navy II 76B-18 pad and was started in late summer and completed in early fall 1997. Weather conditions were mild with some periods of heavier-than-normal rain, but overall moderate ambient temperature conditions. Sandia was participating in this drilling project to evaluate the effectiveness of nitrogen-foamed cement when used to plug loss zones in geothermal wells. The RFM was used by Sandia to document the extent of the lost circulation both before and after applying the foam cement. Data output from the RFM was also provided to the on-site well logger.

After well spudding was completed, the RFM mounting flange was attached to the mud return line pipe. The return line was a 12", schedule-40 steel pipe that was positioned with a 5.0° slope between the pitcher/flow nipple on the rig mud riser and the mud tank. The RFM was located along the return line where access to the RFM, for maintenance and troubleshooting, was available from a sub-deck on the drill rig. Due to the large return-line pipe diameter and the new spacer plate and hinge addition to the RFM assembly, the as-designed stop-plate zero-flow adjustment limits were insufficient to permit the desired adjustment of the float wheel. Therefore, some minor modifications were required to the RFM stop-plate before final float wheel adjustments could be made. When the stop-plate modifications were completed, the RFM was secured to the mounting flange, and the float wheel was adjusted for zero-flow conditions. The counterbalance was adjusted for approximately 750 g wheel down-weight. The RFM flow was calibrated against the inflow flow rate that was measured with a commercial Doppler flowmeter provided by Sandia.

The RFM was used extensively during the 60-day period when mud was used while drilling. Only minor problems with the RFM were encountered, none of which required extensive down time. The float-wheel rotation magnet, as noted during the previous field evaluation test, began to accumulate metallic material on the magnet surface. This was noticed after several weeks of drilling and became more noticeable after casing was installed in the upper 4500' of the well. The protective epoxy coating over the magnet did help prolong the magnet life. However, ferrous metal in the mud return seems inevitable when the wellbore has a steel casing, steel drill pipe, and a steel bit that all are being burnished/rubbed against hard rock or against each other while in use. The buildup of this material on the magnet surface adversely affects the Hall-effect sensor operation by reducing the strength of the magnetic field required to trigger the sensor. Wiping the magnet periodically (once a day) seemed to minimize the problem, but a more permanent solution would be to replace this rotation detection method with one that did not require a magnetic field for operation.


Drilling fluid temperature is a concern during geothermal well drilling operations. To maintain the mud temperatures below 160°F a mud chiller was employed in the drilling fluid system. Frequent use of lost circulation materials during drilling necessitated bypassing the mud chiller, resulting in high temperature gaseous drilling fluids. When the downhole mud temperatures rose significantly, the hot gaseous mud being returned to the surface caused a kick or flashed to steam. This pressure pulse entered the return line pipe, causing the RFM float wheel to again be suddenly forced high enough in the pipe to impact the top of the RFM housing. This pulsing and float wheel impact occurred several times before the mud quality improved and the pulsing subsided. Post-test inspection of the float wheel again revealed bending damage to several fins as a result of impact initiated by the high temperature drilling fluids.

In *Figure 12*, selected data from the above field tests is plotted showing how typical drilling fluid losses were recorded using the RFM.



## Final Design Package

The final design configuration of the RFM is shown in *Figure 13*.



The complete drawing package is presented in Appendix A. Drawing revisions for the addition of the maintenance access hinge to the RFM housing and the new hinge spacer drawing are also included in Appendix A. AutoCADIt files of all mechanical drawings are available upon request. A schematic diagram of the electronic circuit and hardware used by Sandia to power the RFM flow-rate rotary potentiometer and float-wheel rotation Hall-effect magnetic sensor are provided in Appendix A.

Recommendations for RFM installation on a typical return line pipe, normal field maintenance procedures, post-field reconditioning and readiness techniques, and procedures used to prepare the Hall-effect sensor for RFM installation are included in Appendix B.

## **Conclusions**

The RFM has been evaluated thoroughly by Sandia in the laboratory and during drilling operations at both large diameter and slimhole core wells. This instrument provides reliable accurate drilling fluid outflow measurements in a partially filled return line pipe. These measurements can be used to monitor drilling fluid flow rates, from less than 50 gpm to 1000 gpm or more, while drilling a well. The RFM design has undergone continuous improvement during its development process. This has produced a rugged, adaptable instrument that can function reliably under the severe environmental conditions encountered on a geothermal drill rig, while still providing a simple tool that is easy to install, maintain, and operate.

The cost to produce a single prototype RFM is estimated to be approximately \$10,000, however, cost reductions are likely if it is produced in quantity.

The Sandia Geothermal Research Department is available to assist in transferring this technology to potential industry users via training on installation and operation of the RFM and to consult on design features or desired modifications that would lead to improvements and/or wider industry applications.

## References

1. C.C. Carson, and Y.T. Lin, 1982, "The Impact of Common Problems in Geothermal Drilling and Completion," *Geothermal Resources Council Transactions*, Vol. 6, pp. 195-198.
2. G.E. Loeppke, D.M. Schafer, D.A. Glowka, D.D. Scott, M.D. Wernig, and E.K. Wright, 1992 "Development and Evaluation of a Meter for Measuring Return Line Fluid Flow Rates During Drilling," *Sandia Report, SAND91-2607*, Sandia National Laboratories, Albuquerque, NM, 87185-1033.
3. D.M. Schafer, G.E. Loeppke, D.A. Glowka, D.D. Scott, and E.K. Wright, 1992, "An Evaluation of Flowmeters for the Detection of Kicks and Lost Circulation During Drilling," *IADC/SPE 213935, Presented at the IADC/SPE Drilling Conference*, New Orleans, LA, February, 1992.
4. D.A. Glowka, D.M. Schafer, D.D. Scott, M.D. Wernig, and E.K. Wright, 1992, "Development and use of a Return Line Flowmeter for Lost Circulation Diagnosis in Geothermal Drilling," *Geothermal Resources Council Transactions*, Vol. 16, pp. 39-46.
5. G.L. Whitlow, D.A. Glowka, and G.E. Staller, 1996, "Development and Use of Rolling Float Meters and Doppler Flow Meters to Monitor Inflow and Outflow While Drilling Geothermal Wells", *Geothermal Resources Council Transactions*, Vol. 20, pp. 515-521.
6. J.T. Finger and R.D. Jacobson, 1997, "Fort Bliss Exploratory Slimholes: Drilling and Testing", *Sandia Report, SAND97-3075*, Sandia National Laboratories, Albuquerque, NM, 87185-1033.







## **Appendix A**

### **Drawing Package**




- 
- Technical drawing of a rectangular plate with the following dimensions and callouts:
- Overall width:  $22.25 \pm .010$
  - Overall height:  $11.25 \pm .010$
  - Inner width:  $20.000 \pm .010$  (5 EQ SPACES @  $4.000 \pm .010$ )
  - Inner height:  $7.750 \pm .010$
  - Left side dimension:  $1.75 \pm .020$
  - Right side dimension:  $1.75 \pm .03$
  - Bottom left corner dimension:  $1.75 \pm .03$
  - Bottom right corner dimension:  $1.875 \pm .010$
  - Bottom center dimension:  $15.92 \pm .03$
  - Bottom right corner dimension:  $1.88 \pm .03$
  - Top left corner dimension:  $1.75 \pm .020$
  - Top right corner dimension:  $1.156 / 1.176$  TAP DR
  - Bottom right corner dimension:  $1.875 \pm .010$
  - Bottom right corner dimension:  $1.75 \pm .020$
  - Callout 1:  $16 \times .340 / .350$  THRU
  - Callout 2:  $1/8" \times 2 \times$
  - Callout 3:  $1.75 \pm .03$
  - Callout 4:  $1.875 \pm .010$
  - Callout 5:  $1.88 \pm .03$
  - Callout 6:  $1.75 \pm .020$

[illegible]

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. BOND GASKET (ITEM 2) TO COVER (ITEM 1) USING ANY RUBBER BASED ADHESIVE PER THE MANUFACTURER'S INSTRUCTIONS.

PART OR CONTROL NUMBER		REVISIONS				
ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR	APVD
A		GLOWKA/STALLER, 6211		11/15/97		




1		RUBBER, SHEET, BUNA-N, 40 SHORE DUREMETER, .063 THK			2
1	00-S-766	STAINLESS STL, TYPE 304, SHT, .06 THK			1
NA	9900000	GENERAL REQUIREMENTS			
NO REQD	PART/CONTROL NO.	DESCRIPTION/MATERIAL	NOTE	SHEET ZONE	ITEM
PART FILE NAME = Access Cover RFM202					
SHEET	1	2	3	4	5
ISSUE	A				
PART CLASSIFICATION	UNCLASSIFIED				
DRAWING CLASSIFICATION	UNCLASSIFIED				
SIZE	C				
DRAWING NUMBER	RFM-202				
STATUS	FSCH14213 SCALE: 1/1 SHEET 1 OF 1				
	ORIGIN SC-AN1-V1.2a				

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, TYPE 304. ROUND.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301, AFTER MACHINING.

PART OR CONTROL NUMBER		REVISIONS					
ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR	APVD	
A		GLOWKA/STALLER, 6211		11/15/97			



PART CODE FILE NAME = Pivot Bar RFM203									
SHEET	1	2	3	4	5	6	TITLE		
ISSUE	A						PIVOT BAR, RFM II		
PART CLASSIFICATION							TITLE CLASSIFICATION		
UNCLASSIFIED							UNCLASSIFIED		
DRAWING CLASSIFICATION							DRAWING NUMBER		
UNCLASSIFIED							RFM-203		
STATUS							ORIGIN SC-ANI-V1.2a		

GEOMETRIC PRECISION = .0001

3


2

1

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, TYPE 304, PLT, PER QQ-S-766, .250 THK.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301, AFTER MACHINING.

PART OR CONTROL NUMBER	ISS	SHEET ZONE	REVISIONS			
			PREPARED BY	DESCRIPTION	DATE	CHKR APVD
	A		GLOWKA/STALLER, 6211		11/15/97	




PART FILE NAME = Stop Plate RFM204									
SHEET	1	2	3	4	5	6	TITLE		
ISSUE	A						STOP PLATE, RFM II		
PART CLASSIFICATION UNCLASSIFIED							TITLE CLASSIFICATION		
DRAWING CLASSIFICATION UNCLASSIFIED							SIZE	DRAWING NUMBER	
							C	RFM-204	
STATUS							FSCM14213	SCALE 1/1	SHEET 1 OF 1
							ORIGIN	SC-ANI-V1.20	

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
  2. WELD AND INSPECT PER SANDIA SPECIFICATION 9912119, CLASS II, USING E308 ELECTRODES PER AWS A5.4-XX OR ER308 ELECTRODES OR RODS PER AWS A5.9-XX.
  3. PASSIVATE PER SANDIA SPECIFICATION 9904301, AFTER MACHINING.
4. MACHINE SHAFT TO DIAMETER SHOWN OVER THIS LENGTH ONLY.

PART OR CONTROL NUMBER	REVISIONS				
	ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE
A			GLOWKA/STALLER, 6211		11/15/97




1		STAINLESS STL. TYPE 304.			2
1	00-S-763	STAINLESS STL. TYPE 304, RND, .375 DIA			1
NA	9904301	PASSIVATION, STAINLESS STEEL			
NA	9912119	WELDING, STAINLESS STEEL			
NA	9900000	GENERAL REQUIREMENTS			
NO REQ	PART/CONTROL NO	DESCRIPTION/MATERIAL	NOTE	SHEET ZONE	ITEM
		PART FILE NAME = Shaft Wheel RFH205			
		SHEET 1 2 3 4 5 6			
		ISSUE A			
		PART CLASSIFICATION UNCLASSIFIED			
		DRAWING CLASSIFICATION UNCLASSIFIED			
		SIZE D			
		DRAWING NUMBER RFM-205			
		STATUS			
		ORIGIN SC-AN1-V1.2a			

# NOTES

1. GENERAL REQUIREMENTS PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, ROD, TYPE 304 PER 00-S-763
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.
4. MACHINE SHAFT TO DIAMETER SHOWN OVER THIS LENGTH ONLY.

PART OR  
CONTROL NUMBER

REVISIONS					
ISS	SHEET	PREPARED BY	DESCRIPTION	DATE	CHKR
B	206	GLOWKA/STALLER, 6211		9/18/96	
C		REMOVED FLATS, ADDED CSK		9/24/96	
		2 PLCS			



PART FILE NAME = Horizontal Shaft RFM206									
SHEET	1	2	3	4	5	6	TITLE		
ISSUE	C						HORIZONTAL SHAFT, RFM II		
PART CLASSIFICATION							TITLE CLASSIFICATION		
UNCLASSIFIED							RFM II		
DRAWING CLASSIFICATION							DRAWING NUMBER		
UNCLASSIFIED							RFM-206		
FSCM 4213							SCALE 1/1		
STATUS							SHEET 1 OF 1		
ORIGIN SC-ANI-V1.2a									



# NOTES

1. GENERAL REQUIREMENTS PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, TYPE 304 PER QQ-S-763.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.


PART OR  
CONTROL NUMBER

## REVISIONS

ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR	APVD
A		GLOWKA/STALLER, 6211				
B		DELETED D-HOLE, 10-32 THD, AND R, EXTENDED 3/8-24 THD DEPTH, CHANGED LENGTH.		9/24/96		

3/8-24UNF-2B, TO DEPTH SHOWN

.375/.380 THRU



PART CODE FILE NAME = Adapter CB Shaft RFM207											
SHEET	1	2	3	4	5	6	TITLE		TITLE CLASSIFICATION		
ISSUE	B						ADAPTER, CB SHAFT		RFM II		
PART CLASSIFICATION							UNCLASSIFIED				
DRAWING CLASSIFICATION							UNCLASSIFIED				
SIZE							DRAWING NUMBER				
B							RFM-207				
STATUS							ORIGIN SC-AN1-V1.2a				

GEOMETRIC PRECISION = .0001

3


2

1

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STEEL, ANGLE, BAR SIZE, ASTM-A36, 2X1.25X.25.
3. WELD AND INSPECT PER SANDIA SPECIFICATION 9912119, CLASS II, USING E70XX ELECTRODES PER AWS A5.1-XX OR E70S-X ELECTRODES OR RODS PER AWS A5.18-XX.

PART OR CONTROL NUMBER		REVISIONS				
ISS	SHEET	PREPARED BY	DESCRIPTION	DATE	CHKR	APVD
A	1	GLDWA/STALLER, 6211		11/15/97		




PART FILE NAME = Mounting Flange RFM208													
SHEET		1		2		3		4		5		6	
ISSUE		A											
PART CLASSIFICATION										TITLE		TITLE CLASSIFICATION	
UNCLASSIFIED										MOUNTING FLANGE,		RFM II	
DRAWING CLASSIFICATION										SIZE		DRAWING NUMBER	
UNCLASSIFIED										D		RFM-208	
STATUS										FSCM 4213		SCALE 1/2	
										ORIGIN SC-ANI-VI.2a		SHEET 1 OF 1	

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. WELD AND INSPECT PER SANDIA SPECIFICATION 9912119, CLASS II, USING E308 ELECTRODES PER AWS A5.4-XX OR ER308 ELECTRODES OR RODS PER AWS A5.9-XX.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301, AFTER MACHINING.
4. BOND GASKET (ITEM 4) TO COVER FLANGE (ITEM 2) USING ANY RUBBER BASED ADHESIVE, PER THE MANUFACTURER'S INSTRUCTIONS.
5. ALTERNATE METHOD OF FABRICATION, ITEM 3 MAY BE ROLLED AND WELDED.

PART OR CONTROL NUMBER		REVISIONS				
ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR	APVD
B		GLOWKA/STALLER, 6211		9/18/96		

.218/.226, THRU, 6 PLCS  
EQ SPCD WITHIN .010 DN  
A 2.000±.010 DIA. BC.



.298/.312, THRU

1		RUBBER, SHEET, BUNA-N, 40 SHORE DUREMETER, .063 THK			4																																																																												
1		STAINLESS STL, TYPE 304, TUBING, 1.5' OD X .065 WALL	5		3																																																																												
1	00-S-766	STAINLESS STL, TYPE 304, SHT, 16 GA			2																																																																												
1	00-S-766	STAINLESS STL, TYPE 304, SHT, 16 GA			1																																																																												
NA	9904301	PASSIVATION, STAINLESS STEEL																																																																															
NA	9912119	WELDING, STAINLESS STEEL																																																																															
NA	9900000	GENERAL REQUIREMENTS																																																																															
NO REQD	PART/CONTROL NO.	DESCRIPTION/MATERIAL	NOTE	SHEET ZONE	ITEM																																																																												
		<table><tr><td>PART CODE</td><td colspan="5">FILE NAME = Cover Horizontal Shaft RFM209</td></tr><tr><td>SHEET</td><td>1</td><td>2</td><td>3</td><td>4</td><td>5</td><td>6</td><td>TITLE</td><td colspan="2">TITLE CLASSIFICATION</td></tr><tr><td>ISSUE</td><td>B</td><td></td><td></td><td></td><td></td><td></td><td colspan="3">COVER, HORIZONTAL SHAFT, RFM II</td></tr><tr><td colspan="7">PART CLASSIFICATION UNCLASSIFIED</td><td colspan="3"></td></tr><tr><td colspan="7">DRAWING CLASSIFICATION UNCLASSIFIED</td><td>SIZE</td><td colspan="2">DRAWING NUMBER</td></tr><tr><td colspan="7"></td><td></td><td colspan="2">RFM-209</td></tr><tr><td colspan="7"></td><td>FSCM14213</td><td>SCALE: 1/1</td><td>SHEET 1 OF 1</td></tr><tr><td colspan="7">STATUS</td><td colspan="3">ORIGIN SC-ANI-V1.2a</td></tr></table>				PART CODE	FILE NAME = Cover Horizontal Shaft RFM209					SHEET	1	2	3	4	5	6	TITLE	TITLE CLASSIFICATION		ISSUE	B						COVER, HORIZONTAL SHAFT, RFM II			PART CLASSIFICATION UNCLASSIFIED										DRAWING CLASSIFICATION UNCLASSIFIED							SIZE	DRAWING NUMBER										RFM-209									FSCM14213	SCALE: 1/1	SHEET 1 OF 1	STATUS							ORIGIN SC-ANI-V1.2a		
PART CODE	FILE NAME = Cover Horizontal Shaft RFM209																																																																																
SHEET	1	2	3	4	5	6	TITLE	TITLE CLASSIFICATION																																																																									
ISSUE	B						COVER, HORIZONTAL SHAFT, RFM II																																																																										
PART CLASSIFICATION UNCLASSIFIED																																																																																	
DRAWING CLASSIFICATION UNCLASSIFIED							SIZE	DRAWING NUMBER																																																																									
								RFM-209																																																																									
							FSCM14213	SCALE: 1/1	SHEET 1 OF 1																																																																								
STATUS							ORIGIN SC-ANI-V1.2a																																																																										

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: ALUMINUM, PLATE, 6061-T651, PER QQ-A-250/11.
3. ANODIZE PER SANDIA SPECIFICATION 9904102, TYPE II, CLASS II, DYE BLACK.

PART OR  
CONTROL NUMBER

ISS

SHEET  
ZONE

PREPARED BY

## REVISIONS

DESCRIPTION

DATE

CHKR



APVD

A

GLWKA/STALLER, 6211

11/15/97

6-32UNC-2B, TAP DRILL THRU,  
THREADS .38±.03 DEEP FROM  
BOTH SIDES



PART FILE NAME = Spacer Gear Reducer RFM210											
SHEET	1	2	3	4	5	6	TITLE			TITLE CLASSIFICATION	
ISSUE	A						SPACER,			GEAR REDUCER,	
PART CLASSIFICATION							RFM II				
UNCLASSIFIED											
DRAWING CLASSIFICATION							SIZE	DRAWING NUMBER			
UNCLASSIFIED							B	RFM-210			
STATUS							FSCM14213	SCALE: 1/1	SHEET 1 OF 1		
ORIGIN							SC-ANI-V1.2a				

GEOMETRIC PRECISION = .0001

3


2

1

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, TYPE 304, SHEET, PER 00-S-766, .12 THICK.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.

PART OR CONTROL NUMBER		REVISIONS					
ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR	APVD	
A		GLOWKA/STALLER, 6211		11/15/97			




PART FILE NAME = Bracket Gr Rdr Pot RFM211									
SHEET	1	2	3	4	5	6	TITLE		
ISSUE	A						BRACKET, GEAR REDUCER POT, RFM II		
PART CLASSIFICATION							UNCLASSIFIED		
DRAWING CLASSIFICATION							UNCLASSIFIED		
SIZE							C		
DRAWING NUMBER							RFM-211		
FSCN14213							SCALE 1/1		
STATUS							ORIGIN SC-ANI-V1.2a		

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. BOND GASKET (ITEM 2) TO COVER (ITEM 1) USING ANY RUBBER BASED ADHESIVE PER THE MANUFACTURER'S INSTRUCTIONS.

PART OR CONTROL NUMBER		REVISIONS					
ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR	APVD	
A		GLOWKA/STALLER, 6211		11/15/97			



1		RUBBER, SHEET, BUNA-N, 40 SHORE DUROMETER, .063 THK				2																																																																													
1	00-S-766	STAINLESS STL. TYPE 304, SHT, .06 THK				1																																																																													
NA	9900000	GENERAL REQUIREMENTS																																																																																	
NO RECD	PART/CONTROL NO.	DESCRIPTION/MATERIAL	NOTE	SHEET ZONE	ITEM																																																																														
		<table><tr><td>PART CODE</td><td colspan="6">FILE NAME = CB Box Cover RFM213</td></tr><tr><td>SHEET</td><td>1</td><td>2</td><td>3</td><td>4</td><td>5</td><td>6</td><td>TITLE</td><td colspan="2">TITLE CLASSIFICATION</td></tr><tr><td>ISSUE</td><td>A</td><td></td><td></td><td></td><td></td><td></td><td colspan="3">COVER, CB BOX, RFM II</td></tr><tr><td colspan="7">PART CLASSIFICATION</td><td colspan="3">UNCLASSIFIED</td></tr><tr><td colspan="7">DRAWING CLASSIFICATION</td><td>SIZE</td><td colspan="2">DRAWING NUMBER</td></tr><tr><td colspan="7">UNCLASSIFIED</td><td>C</td><td colspan="2">RFM-213</td></tr><tr><td colspan="7">STATUS</td><td>FSM14213</td><td>SCALE: 1/1</td><td>SHEET 1 OF 1</td></tr><tr><td colspan="7"></td><td>ORIGIN</td><td colspan="2">SC-AN1-V1.20</td></tr></table>					PART CODE	FILE NAME = CB Box Cover RFM213						SHEET	1	2	3	4	5	6	TITLE	TITLE CLASSIFICATION		ISSUE	A						COVER, CB BOX, RFM II			PART CLASSIFICATION							UNCLASSIFIED			DRAWING CLASSIFICATION							SIZE	DRAWING NUMBER		UNCLASSIFIED							C	RFM-213		STATUS							FSM14213	SCALE: 1/1	SHEET 1 OF 1								ORIGIN	SC-AN1-V1.20	
PART CODE	FILE NAME = CB Box Cover RFM213																																																																																		
SHEET	1	2	3	4	5	6	TITLE	TITLE CLASSIFICATION																																																																											
ISSUE	A						COVER, CB BOX, RFM II																																																																												
PART CLASSIFICATION							UNCLASSIFIED																																																																												
DRAWING CLASSIFICATION							SIZE	DRAWING NUMBER																																																																											
UNCLASSIFIED							C	RFM-213																																																																											
STATUS							FSM14213	SCALE: 1/1	SHEET 1 OF 1																																																																										
							ORIGIN	SC-AN1-V1.20																																																																											

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, TYPE 304 PER QQ-S-763.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.

PART OR  
CONTROL NUMBER

ISS SHEET  
ZONE

PREPARED BY

## REVISIONS

DESCRIPTION

DATE

CHKR

APVD

GLOWKA/STALLER, 6211

11/15/97

.530/.500

.188±.020

.094±.020

2-56UNC-2B, THRU TO HOLE

.255/.260, THRU

PART CODE										FILE NAME = Ring Horz Shaft Pointer RFM214									
SHEET		1	2	3	4	5	6	TITLE				TITLE CLASSIFICATION							
ISSUE		A						RING, HORZ SHAFT POINTER, RFM II											
PART CLASSIFICATION		UNCLASSIFIED																	
DRAWING CLASSIFICATION		UNCLASSIFIED						SIZE		DRAWING NUMBER									
								B		RFM-214									
STATUS								FSCM14213				SCALE 2/1				SHEET 1 OF 1			
								ORIGIN				SC-AN1-V1.2a							

GEOMETRIC PRECISION = .0001


3

2

1

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, TYPE 304, SHEET, PER QQ-S-766, .060" THK.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.

PART OR CONTROL NUMBER	REVISIONS						
	ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR	APV
	A		GLOWKA/STALLER, 6211		11/15/97		



PART CODE FILE NAME = Splash Plate RFM216									
SHEET	1	2	3	4	5	6	TITLE		TITLE CLASSIFICATION
ISSUE	A						SPLASH PLATE, RFM II		
PART CLASSIFICATION UNCLASSIFIED									
DRAWING CLASSIFICATION UNCLASSIFIED							SIZE	DRAWING NUMBER	
							C	RFM-216	
STATUS							FSCM14213 SCALE: 1/1 SHEET 1 OF 1		
							ORIGIN SC-ANI-V1.20		


GEOMETRIC PRECISION = .0001



# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, TYPE 304, SHEET, PER 00-S-766, .120 THK.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.

PART OR CONTROL NUMBER	REVISIONS						
	ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR	APV
	A		GLOWKA/STALLER, 6211		11/15/97		





PART FILE NAME = Adjusting Tab RFM217											
SHEET	1	2	3	4	5	6	TITLE			TITLE CLASSIFICATION	
ISSUE	A						ADJUSTING TAB,			STOP PLATE, RFM II	
PART CLASSIFICATION							DRAWING NUMBER				
UNCLASSIFIED							C1 RFM-217				
DRAWING CLASSIFICATION							FSCM14213				
UNCLASSIFIED							SCALE: 1/1				
STATUS							ORIGIN SC-AN1-V1.20				

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. WELD AND INSPECT PER SANDIA SPECIFICATION 9912119, CLASS II, USING E302 ELECTRODES PER AWS A5.4-XX OR ER308 ELECTRODES OR RODS PER AWS A5.9-XX.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301, AFTER MACHINING.

PART OR CONTROL NUMBER	REVISIONS					CHKR	APVD
	ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE		
A			GLOWKA/STALLER, 6211		11/15/97		



1	00-S-766	STAINLESS STL, TYPE 304, SHT, .12 THK			2				
2	00-S-766	STAINLESS STL, TYPE 304, PLT, .25 THK			1				
NA	9904301	PASSIVATION, STAINLESS STEEL							
NA	9912119	WELDING STAINLESS STEEL							
NA	9900000	GENERAL REQUIREMENTS							
NO RECD	PART/CONTROL NO.	DESCRIPTION/MATERIAL	NOTE	SHEET ZONE	ITEM				
PART FILE NAME = Shield Adj Screw RFM218									
SHEET		1	2	3	4	5	6	TITLE	TITLE CLASSIFICATION
ISSUE		A						SHIELD, ADJUSTING SCREW, RFM II	
PART CLASSIFICATION UNCLASSIFIED									
DRAWING CLASSIFICATION UNCLASSIFIED						SIZE		DRAWING NUMBER	
						D		RFM-218	
STATUS						FSC# 4213 SCALE: 1/1 SHEET 1 OF 1			
						ORIGIN SC-ANI-V1.20			

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: SOCKET HEAD CAP SCREW, STAINLESS STEEL, HEX DRIVE, 1/4-28UNF, MODIFIED AS SHOWN.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.

PART OR  
CONTROL NUMBER

ISS

SHEET  
ZONE

PREPARED BY

## REVISIONS

DESCRIPTION

DATE


CHKR

APVD

A

GLOWKA/STALLER, 6211

11/15/97



PART CODE FILE NAME = Adjusting Screw RFM 219											
SHEET	1	2	3	4	5	6	TITLE			TITLE CLASSIFICATION	
ISSUE	A						ADJUSTING SCREW, STOP PLATE, RFM II				
PART CLASSIFICATION							UNCLASSIFIED				
DRAWING CLASSIFICATION							UNCLASSIFIED				
SIZE							B				
DRAWING NUMBER							RFM-219				
STATUS							ORIGIN SC-AN1-V1.2a				

GEOMETRIC PRECISION = .0001

3


2

1

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000
2. MODIFY HOFFMAN ENGINEERING CO. 12 X 12 X 6 TYPE 4 "CHINE" BOX. CATALOG NUMBER A-1212CHMF, WITHOUT PANEL, AS SHOWN. MAY BE OBTAINED FROM SUMMIT ELECTRIC SUPPLY 2811 STANFORD NE ALBUQUERQUE, NM 87197

PART OR CONTROL NUMBER		REVISIONS				
REV	DATE	PREPARED BY	DESCRIPTION	DATE	CHKD	APVR
A	11/15/97	GLOVKA/STALLER, 6211				




PART FILE NAME = Counter Balance Box RFM220					
SHEET	1	2	3	4	5
ISSUE	A				
TITLE CLASSIFICATION					
COUNTER BALANCE BOX.					
RFM 11					
PART CLASSIFICATION					
UNCLASSIFIED					
DRAWING CLASSIFICATION					
UNCLASSIFIED					
SIZE DRAWING NUMBER					
RFM-220					
STATUS					
[FROM 4.2] SCALE: 1/1 SHEET 3 OF 1					

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STEEL, PLATE, PER ASTM-A36, .25 THICK.

PART OR CONTROL NUMBER	ISS	SHEET ZONE	REVISIONS			
			PREPARED BY	DESCRIPTION	DATE	CHKR APVD
A			GLOWKA/STALLER, 6211		11/15/97	




PART FILE NAME = Flange Cover RFM221									
SHEET	1	2	3	4	5	6	TITLE		
ISSUE	A						TITLE CLASSIFICATION		
PART CLASSIFICATION							FLANGE COVER		
UNCLASSIFIED							RFM II		
DRAWING CLASSIFICATION							DRAWING NUMBER		
UNCLASSIFIED							RFM-221		
FSCM 4213							SCALE: 1/2		
STATUS							ORIGIN: SC-ANJ-V1.2a		

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: RUBBER, SHEET, BUNA-N, 40 SHORE DUROMETER, .06 THICK.

PART OR CONTROL NUMBER	ISS	SHEET NO.	REVISIONS			
			PREPARED BY	DESCRIPTION	DATE	CHKD APVD
A			GLOWKA/STALLER, 6211		11/15/97	



PART FILE NAME = Flange Gasket RFM222					
SHEET	1	2	3	4	5
ISSUE	A				
PART CLASSIFICATION					
UNCLASSIFIED					
DRAWING CLASSIFICATION					
UNCLASSIFIED					
DRAWING NUMBER					
RFM-222					
FSCM 4213 SCALE 1/2					
SHEET 1 OF 1					
STATUS					
ORIGIN SC-ANI-V1.2a					

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: RUBBER, SHEET, BUNA-N, 40 SHORE DUREMETER, .06 THICK.

PART OR  
CONTROL NUMBER

ISS

SHEET  
ZONE

PREPARED BY

## REVISIONS

DESCRIPTION

DATE

CHKR

APVD

A

GLOWKA/STALLER, 6211

11/15/97

.750±.020

.218/.226, THRU, 6 PLCS  
EQ SPCD WITHIN .010 DN  
A 2.000±.010 DIA BC

.250/.281, THRU

1.000/1.030, THRU

2.56/2.50

PART FILE NAME = CB Box Gasket RFM223												
SHEET	1	2	3	4	5	6	TITLE			TITLE CLASSIFICATION		
ISSUE	A						CB BOX GASKET, RFM II					
PART CLASSIFICATION UNCLASSIFIED												
DRAWING CLASSIFICATION UNCLASSIFIED							SIZE B	DRAWING NUMBER RFM-223				
							FSCM14213	SCALE: 1/1	SHEET 1 OF 1			
STATUS							ORIGIN SC-ANI-V1.2a					

GEOMETRIC PRECISION = .0001

3



2

1

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: ALUMINUM, PLATE, 6061-T651 PER QQ-A-250/11.
3. ANODIZE PER SANDIA SPECIFICATION 9904102, TYPE II, CLASS II. DYE BLACK.

PART OR CONTROL NUMBER	REVISIONS				
	ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE
	A		GLOWKA/STALLER, 6211		11/15/97



FILE NAME = Housing Hall Eff Sensor RFM224					
SHEET	1	2	3	4	5
ISSUE	A				
PART CLASSIFICATION					
UNCLASSIFIED					
DRAWING CLASSIFICATION					
UNCLASSIFIED					
SIZE					
C					
DRAWING NUMBER					
RFM-224					
FSCM14213 SCALE: 2/1 SHEET 1 OF 1					
STATUS					
ORIGIN SC-ANI-V1.20					




# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, SHEET, TYPE 304 PER QQ-S-766, .060 THICK.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.

PART OR  
CONTROL NUMBER

## REVISIONS

ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR	APVD
A		GLDWKA/STALLER, 6211		11/15/97		



FILE NAME = Splash Guard Inside RFM225											
SHEET	1	2	3	4	5	6	TITLE			TITLE CLASSIFICATION	
ISSUE	A						SPLASH GUARD, INSIDE			RFM II	
PART CLASSIFICATION							UNCLASSIFIED				
DRAWING CLASSIFICATION							SIZE		DRAWING NUMBER		
UNCLASSIFIED							B		RFM-225		
STATUS							FSCM14213		SCALE: 1/1		SHEET 1 OF 1
ORIGIN							SC-ANI-V1.2a				

GEOMETRIC PRECISION = .0001

3

2

1

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, SHEET, TYPE 304 PER QQ-S-766, .060 THICK. MAY BE MADE FROM A 3/8" STAINLESS STEEL FENDER WASHER.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.

PART OR  
CONTROL NUMBER

ISS

SHEET  
ZONE

PREPARED BY

REVISIONS

DESCRIPTION

DATE


CHKR

APVD

A

GLOWKA/STALLER, 6211

11/15/97



FILE NAME = Splash Shield Internal RFM226											
SHEET	1	2	3	4	5	6	TITLE		TITLE CLASSIFICATION		
ISSUE	A						SPLASH SHIELD, INTERNAL, RFM II				
PART CLASSIFICATION											
UNCLASSIFIED											
DRAWING CLASSIFICATION							SIZE	DRAWING NUMBER			
UNCLASSIFIED							B	RFM-226			
STATUS							FSCM14213	SCALE: 1/1	SHEET 1 OF 1		
							ORIGIN SC-ANI-V1.2a				

GEOMETRIC PRECISION = .0001

3

2

1

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, SHEET, TYPE 304 PER QQ-S-766, .063 THICK.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.

PART OR  
CONTROL NUMBER

ISS

SHEET  
ZONE

PREPARED BY

## REVISIONS

DESCRIPTION

DATE

CHKR


APVD

A

GLOWKA/STALLER, 6211

11/15/97

.166/.176 THRU, 4 PLCS EO SPCD  
WITHIN  $\pm 0.010$  ON A  $2.125 \pm 0.010$  DIA B.C.



2.53/2.50

.063 STOCK

4.00 $\pm$ .03 SPH R

.063 $\pm$ .020

FILE NAME = Splash Guard Outside RFM227

SHEET	1	2	3	4	5	6	TITLE	TITLE CLASSIFICATION
-------	---	---	---	---	---	---	-------	----------------------

ISSUE	A						SPLASH GUARD, OUTSIDE,	
-------	---	--	--	--	--	--	------------------------	--

PART CLASSIFICATION	UNCLASSIFIED						RFM II
---------------------	--------------	--	--	--	--	--	--------

DRAWING CLASSIFICATION	UNCLASSIFIED	SIZE	B	DRAWING NUMBER	RFM-227
------------------------	--------------	------	---	----------------	---------

	FSCM14213	SCALE: 1/1	SHEET 1 OF 1
--	-----------	------------	--------------

STATUS	ORIGIN	SC-AN1-V1.2a
--------	--------	--------------

GEOMETRIC PRECISION = .0001

3




2

1

# NOTES

1. GENERAL REQUIREMENTS PER SANDIA SPECIFICATION 9900000.
  2. MATERIAL: STAINLESS STEEL TYPE 304 PER QQ-S-766.
  3. WELD AND INSPECT PER SANDIA SPECIFICATION 9912119, CLASS II, USING E308 ELECTRODES PER AWS A5.4-XX OR ER308 ELECTRODES OR RODS PER AWS A5.9-XX.
  4. WELDS SHALL BE WATER TIGHT.
  5. PASSIVATE PER SANDIA SPECIFICATION 9904301, AFTER MACHINING.
  6. APPROXIMATE WEIGHT 2025g (4.5#).
- ▶ TABS MAY BE ONE PIECE IF TABS AND RING ARE SLOTTED FOR LOCATING AND FIXTURING FOR WELDING.

PART OR CONTROL NUMBER	REVISIONS				
	REV	DATE	DESCRIPTION	BY	APP'D
A	1	10/24/96	GLOWKA/STALLER, 8211		



PART FILE NAME = 8 SS Wheel RFM228	TITLE CLASSIFICATION
SHEET 1 2 3 4 5 6	8" SS WHEEL, RFM II
ISSUE A	
PART CLASSIFICATION UNCLASSIFIED	SIZE DRAWING NUMBER RFM-228
DRAWING CLASSIFICATION UNCLASSIFIED	DATE 10/24/96
STATUS	ORIGIN SC-ANI-V1.2a

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: THREADED ROD, STAINLESS STEEL, 3/8-24UNF.

PART OR  
CONTROL NUMBER

ISS

SHEET  
ZONE

PREPARED BY

DESCRIPTION

DATE

CHKR

APVD

A

GLOWKA/STALLER, 6211

11/15/97

.040/.050 SPHERICAL R

.030±.015 X .030±.015  
CHAMFER

(3/8-24UNF-2A)

82°±1°

7.50±.03

PART CODE FILE NAME = Shaft Counterbalance RFM229											
SHEET	1	2	3	4	5	6	TITLE		TITLE CLASSIFICATION		
ISSUE	A						SHAFT, COUNTERBALANCE, RFM II				
PART CLASSIFICATION							DRAWING NUMBER				
UNCLASSIFIED							RFM-229				
DRAWING CLASSIFICATION							SIZE	DRAWING NUMBER			
UNCLASSIFIED							B	RFM-229			
STATUS							FSCM14213		SCALE: 1/1	SHEET 1 OF 1	
ORIGIN							SC-AN1-V1.2a				

GEOMETRIC PRECISION = .0001

3

2

1

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: HEX SOCKET DRIVE SET SCREW, STAINLESS STEEL, 3/8-24UNF X 1.50" LONG, MODIFY AS SHOWN.

PART OR  
CONTROL NUMBER

ISS SHEET  
ZONE

PREPARED BY

## REVISIONS

DESCRIPTION

DATE


CHKR

APVD

A

GLOWKA/STALLER, 6211

11/15/97



PART CODE FILE NAME = Set Screw Pivot Bar RFM230									
SHEET	1	2	3	4	5	6	TITLE		TITLE CLASSIFICATION
ISSUE	A						SET SCREW, PIVOT BAR, RFM II		
PART CLASSIFICATION							UNCLASSIFIED		
DRAWING CLASSIFICATION							SIZE	DRAWING NUMBER	
UNCLASSIFIED							B	RFM-230	
STATUS							FSCM14213	SCALE: 1/1	SHEET 1 OF 1
ORIGIN							SC-AN1-V1.2a		

GEOMETRIC PRECISION = .0001

3


2

1

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: BRASS, ROD, TYPE C360 PER ASTM-B-16, HALF HARD, 3.00" DIA.

PART OR CONTROL NUMBER	REVISIONS					
	ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR APVD
	A		GLDWKA/STALLER, 6211		11/15/97	




PART FILE NAME = 962g Counterbalance RFM231									
SHEET	1	2	3	4	5	6	TITLE		
ISSUE	A						962g COUNTERBALANCE		
PART CLASSIFICATION							TITLE CLASSIFICATION		
UNCLASSIFIED							RFM II		
DRAWING CLASSIFICATION							SIZE	DRAWING NUMBER	
UNCLASSIFIED							C	RFM-231	
STATUS							FSCM14213	SCALE 1/1	SHEET 1 OF 1
							ORIGIN SC-ANI-V1.2a		

GEOMETRIC PRECISION = .0001

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: BRASS, ROD, TYPE C360 PER ASTM-B-16, HALF HARD, 3.00" DIA.

PART OR CONTROL NUMBER	ISS.	SHEET ZONG	REVISIONS			
			PREPARED BY	DESCRIPTION	DATE	CHKR
A			GLDWKA/STALLER, 6211		11/15/97	



PART CODE										FILE NAME = 2886g Counterbalance RFM232									
SHEET		1	2	3	4	5	6	TITLE				TITLE CLASSIFICATION							
ISSUE		A						2886g COUNTERBALANCE				RFM II							
PART CLASSIFICATION										UNCLASSIFIED									
DRAWING CLASSIFICATION										UNCLASSIFIED									
SIZE										DRAWING NUMBER									
C										RFM-232									
STATUS										ORIGIN SC-AN1-V1.2a									

GEOMETRIC PRECISION = .0001

3

2


1



# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, ROUND, TYPE 304 PER QQ-S-763, .250" DIAMETER.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.

PART OR CONTROL NUMBER		REVISIONS					
ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR	APVD	
A		GLOWKA/STALLER, 6211		11/15/97			



PART FILE NAME = Shipping Hook RFM233									
SHEET	1	2	3	4	5	6	TITLE		
ISSUE	A						SHIPPING HOOK, RFM II		
PART CLASSIFICATION							TITLE CLASSIFICATION		
UNCLASSIFIED									
DRAWING CLASSIFICATION							DRAWING NUMBER		
UNCLASSIFIED							RFM-233		
							FSCH14213 SCALE: 1/1 SHEET 1 OF 1		
STATUS							ORIGIN SC-AN1-V1.20		

GEOMETRIC PRECISION = .0001

3

2

1



# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, SHEET, TYPE 304 PER QQ-S-766.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.

PART OR  
CONTROL NUMBER

## REVISIONS

ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR	APVD
A		GLOWKA/STALLER, 6211		11/15/97		



FILE NAME = Magnet Cover Plate RFM234									
SHEET	1	2	3	4	5	6	TITLE		TITLE CLASSIFICATION
ISSUE	A						MAGNET COVER PLATE, RFM II		
PART CLASSIFICATION							UNCLASSIFIED		
DRAWING CLASSIFICATION							SIZE	DRAWING NUMBER	
UNCLASSIFIED							B	RFM-234	
FSCM14213							SCALE: 1/1	SHEET 1 OF 1	
STATUS							ORIGIN SC-AN1-V1.2a		

GEOMETRIC PRECISION = .0001

3

2


1

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. MATERIAL: STAINLESS STEEL, TYPE 304 PER QQ-S-763.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301.

PART OR  
CONTROL NUMBER

REVISIONS						
ISS	SHEET ZONE	PREPARED BY	DESCRIPTION	DATE	CHKR	APVD
A		GLOWKA/STALLER, 6211		11/15/97		



FILE NAME = Sleeve Wheel Bearing RFM235												
SHEET	1	2	3	4	5	6	TITLE			TITLE CLASSIFICATION		
ISSUE	A						SLEEVE, WHEEL BEARING, RFM II					
PART CLASSIFICATION							DRAWING NUMBER					
UNCLASSIFIED							RFM-235					
DRAWING CLASSIFICATION							SIZE	DRAWING NUMBER				
UNCLASSIFIED							B	RFM-235				
STATUS							FSCM14213		SCALE: 1/1		SHEET 1 OF 1	
ORIGIN							SC-AN1-V1.2a					

GEOMETRIC PRECISION = .0001

3


2

1

# NOTES

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. WELD AND INSPECT PER SANDIA SPECIFICATION 9912119, CLASS II, USING E308 ELECTRODES PER AWS A5.4-XX OR ER308 ELECTRODES OR RODS PER AWS A5.9-XX.
3. PASSIVATE PER SANDIA SPECIFICATION 9904301, AFTER MACHINING.

PART OR CONTROL NUMBER	ISS	SHEET ZONE	REVISIONS			
			PREPARED BY	DESCRIPTION	DATE	CHKD APVD
A			GLOWKA/STALLER, 6211		11/13/97	



2	00-S-766	STAINLESS STL. TYPE 304, PLT. .375 THK			2
1	00-S-766	STAINLESS STL. TYPE 304, PLT. .750 THK			1
NA	9904301	PASSIVATION, STAINLESS STEEL			
NA	9912119	WELDING, STAINLESS STEEL			
NA	9900000	GENERAL REQUIREMENTS			
NO	PART/CONTROL NO.	DESCRIPTION/MATERIAL	NOTE	SHEET ZONE	ITEM
		PART FILE NAME = Hinge Spacer RFM236			
		SHEET 1 2 3 4 5 6			
		ISSUE A			
		PART CLASSIFICATION			
		UNCLASSIFIED			
		DRAWING CLASSIFICATION			
		UNCLASSIFIED			
		SIZE			
		DRAWING NUMBER			
		RFM-236			
		FSCM 4213			
		SCALE: 1/2			
		SHEET 1 OF 1			
		STATUS			
		ORIGIN SC-ANI-V1.2a			

1. GENERAL REQUIREMENTS ARE PER SANDIA SPECIFICATION 9900000.
2. WELD AND INSPECT PER SANDIA SPECIFICATION 991219, CLASS II USING E308 ELECTRODES PER AWS A5.4-XX OR E308 ELECTRODES OR RDDS PER AWS A5.9-XX.
3. WELDS SHALL BE WATER TIGHT.
4. PASSIVATE PER SANDIA SPECIFICATION 9904301, AFTER MACHINING.

6 REF

250 ± 0.020

50 ± 0.03

3X, 6-32UNC-2B, 14HRU

6.250 ± 0.10

2X, 6-32UNC-2B X 50 ± 0.03 DEEP

1.250 ± 0.020

1.750 ± 0.10

25, 1.250 ± 0.020




25, 3.500 ± 0.10

1.250 ± 0.020

Technical drawing of a mechanical part, likely a valve or fitting, showing a cross-section with dimensions and callouts.

Dimensions and Callouts:

- Top horizontal dimension:  $8.750 \pm 0.010$
- Top right horizontal dimension:  $4.375 \pm 0.020$
- Top right horizontal dimension:  $1.188 \pm 0.020$
- Top right corner chamfer:  $1/8"$
- Top left callout:  $3X, R$
- Right side callout:  $10-32UNF-2$   
 $6$  PLCS EO  
DN  $A$  2.000  
BOTH SIZES
- Right side callout:  $3/16"$
- Right side callout:  $2X, \phi 2.50$  STK
- Bottom left callout:  $2X, 6.38 \pm 0.03$
- Bottom left callout:  $2X, \phi 2.23 \pm 0.27$
- Bottom left callout:  $2X, 1.25 \pm 0.020$
- Bottom left callout:  $250 \pm 0.020$
- Bottom left callout:  $(6.38)$
- Bottom right callout:  $(1.063)$
- Bottom right callout:  $4$
- Bottom left callout:  $1/4-28UNF-2B$   
THRU,  $\phi 28$  MAX  
WELD SPOTFACE



4	00-5-763	STAINLESS STL. TYPE 304, FLAT, 375X.75	8																																								
2	00-5-763	STAINLESS STL. TYPE 304, RHD, 50 DIA	7																																								
1	00-5-763	STAINLESS STL. TYPE 304, FLAT, 25X 50	6																																								
1	00-5-763	STAINLESS STL. TYPE 304, 30.	5																																								
2	00-5-763	STAINLESS STL. TYPE 304, RHD, 25 DIA	4																																								
1	00-5-766	STAINLESS STL. TYPE 304, PLT, 25 THK	3																																								
2	00-5-766	STAINLESS STL. TYPE 304, PLT, 25 THK	2																																								
1	00-5-766	STAINLESS STL. TYPE 304, PLT, 18 THK	1																																								
NA	9904301	PASSIVATION, STAINLESS STEEL																																									
NA	991219	WELDING, STAINLESS STEEL																																									
NA	9900000	GENERAL REQUIREMENTS																																									
NO	PART/CONTROL NO	DESCRIPTION/MATERIAL	NOTE 3052 1 ITEM																																								
<table border="1"> <tr> <td>PART CODE</td> <td>FILE NAME = Housing Wheel, RFM 237</td> <td>TITLE</td> <td>TITLE CLASSIFICATION</td> </tr> <tr> <td>S-ECT</td> <td>1 2 3 4 5 6</td> <td></td> <td></td> </tr> <tr> <td>ISSUE</td> <td>A</td> <td></td> <td></td> </tr> <tr> <td>PART CLASSIFICATION</td> <td></td> <td>HOUSING, WHEEL, HINGE, RFM II</td> <td></td> </tr> <tr> <td></td> <td>UNCLASSIFIED</td> <td></td> <td></td> </tr> <tr> <td>DRAWING CLASSIFICATION</td> <td></td> <td>SIZE DRAWING NUMBER</td> <td></td> </tr> <tr> <td></td> <td>UNCLASSIFIED</td> <td>E</td> <td>RFM-237</td> </tr> <tr> <td></td> <td></td> <td></td> <td>1/32X 4 1/2 X 3/16 SCALE 1/8" = 1"</td> </tr> <tr> <td></td> <td></td> <td></td> <td>(ORIGIN SC-AN)-V1.0A</td> </tr> <tr> <td></td> <td>STATUS</td> <td></td> <td></td> </tr> </table>				PART CODE	FILE NAME = Housing Wheel, RFM 237	TITLE	TITLE CLASSIFICATION	S-ECT	1 2 3 4 5 6			ISSUE	A			PART CLASSIFICATION		HOUSING, WHEEL, HINGE, RFM II			UNCLASSIFIED			DRAWING CLASSIFICATION		SIZE DRAWING NUMBER			UNCLASSIFIED	E	RFM-237				1/32X 4 1/2 X 3/16 SCALE 1/8" = 1"				(ORIGIN SC-AN)-V1.0A		STATUS		
PART CODE	FILE NAME = Housing Wheel, RFM 237	TITLE	TITLE CLASSIFICATION																																								
S-ECT	1 2 3 4 5 6																																										
ISSUE	A																																										
PART CLASSIFICATION		HOUSING, WHEEL, HINGE, RFM II																																									
	UNCLASSIFIED																																										
DRAWING CLASSIFICATION		SIZE DRAWING NUMBER																																									
	UNCLASSIFIED	E	RFM-237																																								
			1/32X 4 1/2 X 3/16 SCALE 1/8" = 1"																																								
			(ORIGIN SC-AN)-V1.0A																																								
	STATUS																																										



## **Appendix B**

### **Recommended Procedures**

### **Recommended Procedures for RFM Field Installation**

1. Install RFM on top of drilling fluid return line pipe between pitcher/flow nipple on well mud riser and mud tank shaker box.
2. Downslope angle of return pipe needs to be between 2° and 15° (8° to 12° works best).
3. Return line pipe needs an opening for RFM mounting flange. Torch cutting is acceptable. Opening should be located on pipe for access to the RFM during installation and service (i.e.-proximity to a work deck or sub-floor).
4. Opening for mounting flange needs to be sized to outside perimeter of mounting flange, not inside perimeter.
5. Mounting flange needs to be positioned in the pipe cutout only far enough to be welded. Use continuous weld while maintaining same downslope angle as pipe and level side to side with a bubble level tool.
6. The RFM can be tilted 90° for maintenance or removal from the return pipe. The direction of rotation needs to be determined before the RFM and hinge spacer are installed. The direction of rotation will be dictated by the side of the pipe that offers the easiest access to the RFM. The hinge portion of the hinge spacer will be on the opposite side of the pipe from this established access. The RFM NEMA 4 enclosure and internal components need to be mounted on the access side of the RFM.
7. Install a rubber gasket and RFM hinge spacer on top of the mounting flange. Bolts are inserted through the mounting flange tabs into the hinge spacer. (thread lubricant, such as Loctite #771, should be used on all bolts during installation).
8. Ensure that j-hook is securing RFM wheel in full up-position inside RFM housing before mounting RFM.
9. Mount RFM and a rubber gasket on top of hinge spacer. Install pins between RFM hinges and hinge spacer hinges, then insert and tighten bolts to secure RFM to hinge spacer.
10. Release j-hook and lower wheel slowly into pipe.
11. While spinning the wheel by hand, adjust the RFM stop plate to raise the wheel just enough to not touch the bottom of the pipe I.D. The RFM can detect lower flow rates if the wheel is close to the pipe I.D. bottom.



12. Check wheel weight for approximately 750 grams of down-weight. Attach a weight scale through the top access port on the RFM housing to the wheel mounting shaft. This measurement needs to be taken when the wheel mounting shaft is parallel to the RFM housing flange. If the wheel weight is not 750 grams, adjust the counter balance weight, located inside the NEMA 4 enclosure, until the 750 gram wheel down-weight is obtained.
13. The signal/power cable connections at the RFM are made inside the NEMA 4 enclosure to a WAGO terminal strip. The electrical feed-through on the back of the box is sized for a 4-pair cable.
14. The other end of the signal/power cable is connected to a terminal block in the RFM instrumentation box. This box is normally located some distance from the RFM, in the area of the data-acquisition computer. Wiring the signal/power cable at the RFM and instrumentation box is done according to the associated RFM wiring schematics.
15. Signal/power checkout normally requires two people, one person to monitor the data acquisition computer and instrumentation box, the other to manually spin the RFM wheel to verify Hall-effect rotation sensor operation and pivot the wheel mounting shaft to verify that the angle potentiometer is working. One person can do the signal/power checkout if the data-acquisition computer is concurrently taking data while the RFM is manually exercised.

## **Recommended Procedures for RFM Field Maintenance**

Normally problems with the RFM in the field are minimal. The table below can serve as a guide if problems do occur.

**Caution:** Care should be exercised when working on a RFM attached to a return-line pipe, since temperatures of the drilling fluid flowing in the return-line may be high enough to burn exposed skin.

**TABLE I - TROUBLESHOOTING A RFM**

<b><u>PROBLEM</u></b>	<b><u>POSSIBLE CAUSE/FIX</u></b>
1. NO ROTATION SIGNAL AND/OR ANGLE VOLTAGE	CHECK THAT ALL POWER SWITCHES ON THE RFM ELECTRICAL INSTRUMENTATION BOX ARE ON AND THAT THE BOX IS CONNECTED TO 110VAC POWER.
2. NO ROTATION SIGNAL	VERIFY THAT THE WHEEL IS ROTATING FREELY VIA THE WHEEL INSPECTION COVER ON THE RFM HOUSING.
3a. NO ROTATION SIGNAL & WHEEL IS ROTATING	THE HALL-EFFECT ROTATION SENSOR MAGNET MAY HAVE PIECES OF FERROUS MATERIAL MAGNETICALLY ATTACHED. USUALLY A SWIPE ACROSS THE MAGNET FACE IS SUFFICIENT TO CLEAN ANY FERROUS MATERIAL OFF THE MAGNET.
3b.	EROSION OF THE MAGNET FACE EXPOSED TO THE DRILLING FLUIDS CAN OCCUR IF IT DOES NOT HAVE A PROTECTIVE COATING. EPOXY COATINGS OR NICKEL PLATING OF THE MAGNET FACE WILL EXTEND THE MAGNET LIFE DRAMATICALLY.
3c.	VERIFY THAT THE FREQUENCY-TO-VOLTAGE CONVERTER IS RECEIVING SIGNAL PULSES FROM THE RFM AND CONVERTING THEM TO A VOLTAGE OUTPUT FOR THE DATA-ACQUISITION COMPUTER.
4. ANGLE VOLTAGE CHANGES (FROM INITIAL NO-FLOW SETTING)	CHECK ALL SHAFT COUPLINGS INSIDE THE RFM STEEL ENCLOSURE BOX FOR TIGHTNESS. IT IS RECOMMENDED TO MARK ALL COUPLINGS AND SHAFTS INSIDE THE STEEL ENCLOSURE BOX WITH A PERMANENT MARKER. ANY SLIPPAGE BETWEEN THE COUPLINGS AND SHAFTS THEN WILL BE READILY APPARENT.

Note: The RFM can be tilted 90° on its side for maintenance purposes or to remove it temporarily from the return-line pipe without affecting drilling operations.

Note: The wheel and pivot shaft bearings have not been a source of problems to date, but should be inspected and/or replaced between RFM applications.

**Recommended Procedures for RFM Post Field Reconditioning and/or Initial Checkout**

1. Clean RFM thoroughly inside and out with water.
2. Inspect and, if required, replace wheel bearings with identical stainless steel bearings. Preload on bearings should be approximately 1/8-turn tighter after initial freeplay is adjusted out. The 1/8-turn preload should not change how easily the wheel turns when spun by hand. If it does, then readjust preload as necessary.
3. Visually check wheel for bent fins or any irregularities and straighten if necessary.
4. Visually check Hall-effect sensor housing and cable for any deterioration.
5. Replace magnet paying attention to polarity, since the Hall-effect sensor only actuates on a North pulse. The replacement magnet needs to be epoxy coated or nickel plated for protection if a blank magnet retaining cover is not used. If an epoxy coating is used, apply the epoxy through the hole in the magnet retaining cover after the magnet and cover is installed and only thick enough to be flush with the top of the cover.
6. Check pivot-shaft bearings for any roughness, freeplay, or seal leakage. Again, if required, replace with identical stainless steel bearings.
7. Replace rotary potentiometer (approximate cost \$130) if the RFM has been in service for 2 months or more. Potentiometer can be reused if it is adjusted to use a new internal operating area, but this is not recommended.
8. Use thread adhesive (i.e. Loctite #242) on all screws associated with the rotary potentiometer, magnet retaining cover screws, and wheel bearing cover screws.
9. Use thread lubricant (i.e. Loctite #771) on all other screws and bolts.

### **Recommended Procedures for Preparation and Installation of the RFM Hall-Effect Magnetic Sensor**

1. The lead-in wires are 24-gauge, Teflon-coated, and are dipped in etching fluid (i.e. Gore tetra-etch) for better adhesion of coating materials to the Teflon.
2. A two-part synthetic-rubber polysulfide coating (i.e. Flame Master CS3100) is applied to the junction terminals of the wires and Hall-effect sensor to prevent the terminals from shorting to each other or to the housing.
3. The Hall-effect sensor is installed in the housing with its nomenclature (lettering) facing outward in the direction of the magnet and positioned approximately 1/16" from the bottom of the machined slot in the housing.
4. Aluminum oxide epoxy filler (i.e. Shell Epon 828, cured with Fisher diethanol amine) is used to pot the Hall-effect sensor and wires into the housing. A cure time of 24 hours is required.

**Distribution:**

Bill Turner, Managing Director  
APS Technology  
P O Box Q  
Hellertown, PA 18055

Nic Nickels  
Baker Hughes INTEQ  
5610 Skyline Blvd., Suite D  
Santa Rosa, CA 95403

Gene Polk  
Manager, Customer Service  
Baroid Drilling Fluids, Inc.  
2220 First Street  
Albuquerque, NM 87102-1041

Roger Magee  
Boart Longyear Company  
32 Stokes Drive  
P.O. Box 1000  
Dayton, NV 89403

John M. Mastor, B.S.M.E.  
Manager, Nevada - Western Zone  
Boart Longyear Company  
32 Stokes Drive  
P O Box 1000  
Dayton, NV 89403

Mike Jagoe, General Manager,  
Boart Longyear Company  
Contracting Services  
2340 West 1700 South  
P.O. Box 27314  
Salt Lake City, Utah 84127-0314

Don Anderson, Plant Manager  
Boart Longyear Company  
2340 West 1700 South  
P O Box 27314  
Salt Lake City, Utah 84127-0314

Patrick "Paddy" J. Langan  
Product Manager  
Boart Longyear Company  
2340 West 1700 South  
P O Box 27314  
Salt Lake City, Utah 84127-0314

Marita Allan, B.Sc. (Hons). Ph.D.  
Brookhaven National Laboratory  
Department of Applied Science  
Building No. 526  
Upton, NY 11973

Lawrence E. Kukacka  
Leader, Process Materials Group  
Brookhaven National Laboratory  
Process Sciences Division  
Department of Applied Science  
Upton, L.I., New York 11973

Alex Schreiner  
CalEnergy Company, Inc.  
900 N. Heritage Dr., Bldg. D  
Ridgecrest, CA 93555

Fred Pulka  
CalEnergy Operating Company  
950 W. Lindsey Road  
Calipatria, CA 92233

Paul Spielman  
CalEnergy Company, Inc.  
900 N. Heritage Dr., Bldg. D  
Ridgecrest, CA 93555

Todd Van de Putte  
CalEnergy Company, Inc.  
900 N. Heritage Dr., Bldg. D  
Ridgecrest, CA 93555

Mark Walters  
CalEnergy Company, Inc.  
900 N. Heritage Dr., Bldg. D  
Ridgecrest, CA 93555

Brian Berard  
CalEnergy Company, Inc.  
900 N. Heritage Dr., Bldg. D  
Ridgecrest, CA 93555

Marc Steffen  
Calpine Corporation  
1160 N. Dutton Ave., Suite 200  
Santa Rosa, CA 95401

Elwood Champness  
Drill Cool Systems, Inc.  
Tom Champness  
627 Williams Street  
Bakersfield, CA 93305

Bill Anderson  
Epoch, Inc.  
P.O. Box 1284  
Magnolia, TX 77353

Dan Basko  
Epoch, Inc.  
P.O. Box 1284  
Magnolia, TX 77353

Jim Combs, Ph.D.  
Geo Hills Associates  
27790 Edgerton Road  
Los Altos Hills, CA 94022

Perle M. Dorr  
Geothermal Energy Association  
Director of Outreach Programs  
122 C Street, N W, Suite 400  
Washington, DC 20001-2109

Mike Noel  
Halliburton Energy Services  
P.O. Box 80118  
Bakersfield, CA 93380-0118

Rusty Lockman, Technical Supervisor  
Halliburton Energy Services  
P.O. Box 80118  
Bakersfield, CA 93380-0118

Mike Barry  
Geothermal Operations Engineer  
Halliburton Energy Services  
34722 7<sup>th</sup> Standard Road  
P O Box 80118  
Bakersfield, CA 93380-0118

Joe G. Garcia  
Wellsite Engineer  
Halliburton Energy Services  
34722 7<sup>th</sup> Standard Road  
P O Box 80118  
Bakersfield, CA 93380-0118

Gary Shinabarker  
Service Coordinator  
Halliburton Energy Services  
P O Box 80118  
Bakersfield, CA 93380-0118

Mike Devine  
Service Supervisor  
Halliburton Energy Services  
1990 Hays Lane  
P O Box 2117  
Woodland, CA 95776

Greg Taylor  
Layne Christensen Corp.  
P.O. Box 3077  
Salt Lake City, UT 84130-0777

Donna M. Smith, Ph.D.  
Program Manager,  
Los Alamos National Lab  
Extractive Industry Technologies  
P O Box 1663, MS-C331  
Los Alamos, NM 87545

Andrea R. Pistone  
Marketing Specialist  
Los Alamos National Lab  
Extractive Industry Technologies  
P O Box 1663, MS-C331  
Los Alamos, NM 87545

Keith Womer  
Martin-Decker Totco  
1200 Cypress Creek Road  
Cedar Park, TX 78613-3614

Mitch Wood  
Martin-Decker Totco  
1200 Cypress Creek Road  
Cedar Park, TX 78613-3614

Ray Ravitz  
M-I Drilling Fluids, Co.  
6301 Seven Seas Avenue  
Bakersfield, CA 93308

Tom Heinz  
M-I Drilling Fluids Co.  
6301 Seven Seas Avenue  
Bakersfield, CA 93308

Bob Johnson  
McAllister Petroleum Services Ltd.  
P.O. Box 860  
Ventura, CA 93002

Brian Tarr, Engineering Consultant  
Mobil Technology Company  
Exploration and Producing Technical  
Center  
P O Box 650232  
Dallas, TX 75265-0232

Nabors Drilling USA, Inc.  
Ron Cleveland  
P.O. Box 418  
Bakersfield, CA 93302

Carl R. Peterson, Director  
NADET Institute  
MIT E40-481  
77 Massachusetts Avenue  
Cambridge, MA 02139

Peter H. Smeallie  
Consultant  
NADET Institute  
600 Woodland Terrace  
Alexandria, VA 22302

David S. Pixton  
Novatek  
2185 South Larsen Pkwy  
Provo, UT 84606

Eugene C. Pollard, Jr.  
Operations Superintendent  
Ocean Drilling Program  
Texas A&M University Research Park  
1000 Discovery Drive  
College Station, TX 77840

Walter R. (Dick) Benoit  
Resource Manager  
Oxbow Power Services, Inc.  
5250 South Virginia Street, Suite 304  
Reno, NV 89502

Pajarito Enterprises  
John Rowley  
3 Jemez Lane  
Los Alamos, NM 87544

Phillip (Eddie) Pruett, President  
Pruett Industries International  
8915 Rosedale Highway  
Bakersfield, CA 93312

Bill Rickard P.E.  
Resource Group  
40201 Sagewood Dr.  
P.O. Box 11898  
Palm Desert, CA 92255

Jim Horn  
Santa Fe Geothermal, Inc.  
Two Lincoln Centre  
5420 LBJ Freeway, Suite 1100  
Dallas, TX 78240-2648

P. J. (Pat) Gill  
Laboratory Manager, Western Division  
Schlumberger (Dowell)  
P O Box 5818  
Denver, CO 80217

Bud Frederick  
Engineering & Marketing Manager  
Schlumberger (Dowell)  
P O Box 81437  
Bakersfield, CA 93380-1437

Ron Wilson  
Cement Cell Leader  
Schlumberger (Dowell)  
6120 Snow Road (93308)  
P O Box 81437  
Bakersfield, CA 93380-1437

James Hanson  
Smith Drilling and Completion  
P.O. Box 1231  
Healdsburg, CA 95448

John Campbell  
Smith International, Inc.  
16740 Hardy Street  
P O Box 60068  
Houston, TX 60068

Alan Frazer, President  
Tecton Geologic, Inc.  
5610 Skylane Blvd., Suite A  
Santa Rosa, CA 95403

Louis Capuano  
Thermasorce  
P.O. Box 1236  
Santa Rosa, CA 95402

Marshall Pardey  
Tonto Drilling Services, Inc.  
2200 South 4000 West  
Salt Lake City, UT 84126

Larry Pisto, Manager - Core Division  
Tonto Drilling Services, Inc.  
2200 South 4000 West  
P O Box 25128  
Salt Lake City, UT 84120

Tsvi Meidav  
Trans Pacific Geothermal  
1901 Harrison St., Suite 1590  
Oakland, CA 94612

Douglas Jung, P. E.  
Two-Phase Engineering and Research,  
Inc.  
3209 Franz Valley Road  
Santa Rosa, CA 95404

Dennis L. Nielson, Ph.D.  
The University of Utah  
Energy & Geoscience Institute  
Department of Civil and Environmental  
Engineering  
423 Wakara Way  
Salt Lake City, UT 84108

Michael E. Utt, P.E.  
Unocal Corporation  
Exploration & Production Technology  
14141 Southwest Freeway  
Sugar Land, Texas 77478-3435



Tim Anderson  
Unocal Geothermal  
1300 North Dutton Avenue  
Santa Rosa, CA 95401

Paul E. Grabowski  
U. S. Department of Energy  
1000 Independence Avenue, S.W.  
EE-12  
Washington, DC 20585

Allan Jelacic  
U. S. Department of Energy  
1000 Independence Avenue, S.W.  
EE-12  
Washington, DC 20585

Lewis W. Pratsch  
U. S. Department of Energy  
1000 Independence Avenue, S.W.  
EE-12  
Washington, DC 20585

Marshall J. Reed  
U. S. Department of Energy  
1000 Independence Avenue, S.W.  
EE-12  
Washington, DC 20585

Joe Turk  
Weatherford Enterra  
1000 Church Road  
Rio Vista, CA 94571

**Internal Distribution:**

MS-1033 D. A. Glowka (6211)  
MS-1033 G. E. Staller (6211) 20 copies  
MS-1033 J. J. Westmoreland (6211)  
MS-1033 G. L. Whitlow (6211)  
MS-1033 E. K. Wright (6211)  
MS-9018 Central Technical Files, 8940-  
2  
MS-0899 Technical Library, (4916) 2  
copies  
MS-0619 Review & Approval Desk,  
(12690)  
for DOE/OSTI 2 copies